166

ENGINEERING DEPARTMENT.

KADUR DIVISION.

Dated 29th December 1919.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur Division, up to 22nd January 1920, for repairing Yellambalse Anicut and channels, Kadur Taluk. An approximate estimate of quantities is given below. These quadtities are not guaranteed. The work should be completed by the end of May 1921.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur between the hours of 11 A.M. and 5 P.M., on office days

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tender should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for repairing Yellambalse Anicut and channels, Kadur Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of detailed quantities for repairing the Yellambalase Anicut and channels, Kadur Taluk.

Items of work	Per	Quantity
Channel—		
Earthwork clearing silt in the channel and using earth to bund with forming and tamping.	C. yd.	33,269
Examining and repairing existing madaboy	Each	14
Repairing existing cart bridges	,,	8
Do relieving weirs	,,	5
Painting mile stones	,,	6
Do furlong stones	,,	39
Do grade stones	,,	132
New furlong stones	,,	1
Painting madaboy number stones	,,	14
Anicut—		
Bund excavation cutting work to revetment	C. yd.	462
New rough stone revetment	,,	257
Breaching weir—		
Excavation earthwork cutting for apron	,,	1,017
Concrete in surki mortar	,,	2,089
Burnt brick in surki mortar	C. ft.	5,583
Burnt stone slabs dressed 6" thick	S. ft.	1,094
Refixing old stone slabs	,,	30
Surki plastering	S. yd.	7·90
New rough stone work to apron	C. yd.	372
Clearing draft below apron, lump sum	Lump sum	
Repairs to existing weir apron, lump sum	Lump sum	
Repairs to anicut—		
Earthwork and forming bund with turfing and consolidation including excavation of surki wall.	Lump sum	
Bailing out water	Lump sum	
Concrete in surki mortar	C. ft.	300
Burnt brick in surki mortar	,,	1,211
Burnt stone slabs	,,	120
Plastering with cement	S. yd.	6·80
Dismantling existing body wall for inserting bond slabs and surki plastering ..	No.	10
ew stone apron	C. yd.	300
Old stone work	,,	219
Dismantling old stone work to make gapat breach	,,	16
Do body wall do	C. ft.	240
Filling holders as shown in cross section	C. yd.	36

H. R. VENKATASUBBA RAO
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

AMRUTMAHAL DEPARTMENT.

Notice dated 24th December 1919.

Sealed tenders for the supply of good and cleaned "Kulthi" required for the horses, etc., at the Kunigal Stud Farm, from 1st March 1920 to 28th February 1921, will be received up to 2 P.M. on Saturday the 31st January 1920 in the office of the Superintendent, Amrutmahal Department, at Mysore.